







### ADVANCED BUSINESS CONSULTANTS

AN ISO 9001:2015, ISO 14001 & BS OHSAS 18001 CERTIFIED COMPANY

P.O. BOX: 698, PC: 133, MUSCAT SULTANATE OF OMAN

TEL: +968- 24792173 / 24792174 FAX: +968- 24792175

### Submitted to



# JINDAL SHADEED IRON & STEEL LLC **SULTANATE OF OMAN**

**AUGUST 2022** 

**PROJECT PROFILE** FOR SETTING UP **REBAR EPOXY COATING PLANT** 

# **CONTENTS**

1.	PROJECT BRIEF	1
2.	MARKET ANALYSIS	2
2.1.	REBAR EPOXY COATING- OVERVIEW	2
2.1.1.	Advantages of Epoxy Coated Rebar	3
2.1.2.	Epoxy Rebar Coating - Applications	4
2.2.	ESTIMATE OF DOMESTIC DEMAND	5
2.2.1.	Local Producers	5
2.2.2.	Estimated Demand / Consumption	5
2.3.	Demand Projection	6
2.4.	COMPETITION ANALYSIS	6
2.4.1.	Local Players	6
2.5.	MARKETING MIX STRATEGY OF COMPETITORS	7
2.5.1.	Services	7
2.5.2.	Pricing	7
2.5.3.	Promotion	7
2.5.4.	Trade Credit	7
2.5.5.	Distribution	7
2.6.	PROPOSED MARKETING MIX STRATEGY FOR THE COMPANY	7
2.6.1.	Product Mix	7
2.6.2.	Target Market	7
2.6.3.	Pricing	8
2.6.4.	Promotion	8
2.6.5.	Distribution	8
2.7.	Projected Market Share	9
3.	TECHNICAL ANALYSIS	10
3.1.	LOCATION	10
3.2.	MANUFACTURING PROCESS	10
3.3.	Land & Building	13
3.4.	Machinery	13
3.4.1.	Machinery Suppliers	13
3.5.	Plant Capacity	14
3.6.	VEHICLES	14
3.7.	RAW MATERIALS AND CONSUMABLES	14

6	CONCLUSION	24
<b>5.</b>	FACTORS TO CONSIDER BEFORE PROJECT IMPLEMENTATION	23
4.9.	SENSITIVITY ANALYSIS	22
4.8.	KEY APPRAISAL CRITERIA	
4.7.	NET PROFIT AND PROFITABILITY ANALYSIS	22
4.6.	Cost Ratios	21
4.5.	SALES REALIZATION	21
4.4.	INCOME TAX	21
4.3.7.	Loan & Interest Calculation	21
4.3.6.	Depreciation	20
4.3.5.	Administrative Expenses	20
4.3.4.	Factory Overheads	20
4.3.3.	Salaries & Wages	20
4.3.2.	Utilities	20
4.3.1.	Raw Materials	19
4.3.	COST OF SALES.	19
4.2.	MEANS OF FINANCE	18
4.1.7.	Working Capital	17
4.1.6.	Contingency & Escalation	17
4.1.5.	Pre-Operative Expenses	17
4.1.4.	Furniture & Office Equipment	17
4.1.3.	Vehicles & Internal Transport	16
4.1.2.	Plant & Machinery	16
4.1.1.	Land & Building	16
4.1.	Project Cost	16
4.	FINANCIAL ANALYSIS	16
3.10.	PROJECT IMPLEMENTATION	15
3.9.	Manpower	15
3.8.2.	Electricity	15
3.8.1.	Water	14
3.8.	UTILITIES	14

# **ANNEXURE - FINANCIAL WORKINGS**

# 1. PROJECT BRIEF

This report relates to a study on the feasibility of setting up a Rebar Epoxy Coating unit in the Sultanate of Oman. The following is the Brief illustration of the project:

Name of Product/So	ervice	Rebar Epoxy Coating	
Domestic Market Po	otential (as of 2022)	122,885 Tons per Annum	
Capacity of the Proj	ect	25,590 Tons per Annum	
Total Investment		RO 918,000	
Equity Investment		RO 367,200	
Key Appraisal Crite	eria:		
IRR on total investm	nent	14.41%	
IRR on Equity		22.63%	
Payback period of T	otal Investment	6 years 7 months	
Payback period on 6	equity	5 years 9 months	
Break Even Point (a	s % of Capacity)	74	
Cash Break Even Po Capacity)	oint (as % of	67.5	
Debt Equity Ratio		1.5:1	
DSCR		2.247	
Mannayyan	Total	75	
Manpower	Nationals	26	

#### 2. MARKET ANALYSIS

#### 2.1. REBAR EPOXY COATING- OVERVIEW

Rebar coatings are protective coatings applied to rebars to protect them against corrosion and avoid their rapid deterioration due to extremes of temperature. Rebar coatings are available in the form of a dry powder at the normal atmospheric temperature, which is then applied to the rebar using electrostatic charge.

Fusion-bonded epoxy coatings for rebar, commonly known as FBE coatings, are primarily employed for protection against corrosion. These coatings are in the form of dry powder at normal atmospheric temperature. The powder is applied electrostatically to the surface of cleaned hot steel bars and cured to form a protective film after undergoing various chemical processes. The epoxy-coated rebars last longer due to the protective film and thereby contribute to the quality of construction. A good quality Epoxy Coated TMT Bar must have a uniform coating, chemically stable and adhere to a high pH environment.

Epoxy Coated Rebar acts as a barrier system intended to prevent moisture and chlorides from eroding the surface of the reinforcing bar. Epoxy Coated Rebar is used to provide additional protection in environments where reinforcements are subjected to accelerated corrosion. The use of these bars is significantly increasing as the concrete use is becoming more diverse in corrosion-prone areas. Epoxy coatings provide optimum protection against abrasion, turbulence, corrosive fluids and extreme temperatures. Epoxy coated rebar is not only durable but also resistant to many corrosive substances. It offers corrosion resistance especially for marine structures.

A typical polymer coated rebar is as shown below:



# 2.1.1. Advantages of Epoxy Coated Rebar

Plain steel is subject to corrosive forces over time. As rust forms on the outside of the embedded rebar, it exerts an increasing amount of pressure on the surrounding concrete. This can cause the concrete slab to spontaneously crack, while also making the concrete more vulnerable to damage caused by blows and compressive forces. The surface of the concrete may develop patches of spalling, creating rough and unattractive areas.

Epoxy-coated rebar prevents corrosion and the problems that it causes and offers a multitude of advantages.

- The coating layer is firm and stable which offers good tenacity and high insulation
- The coating layer is corrosion-resistant
- Lower maintenance cost
- Lower lifecycle costs over time
- Uniform thickness of coating which adds to the quality of production
- Acts as an insulator for electrochemical cells and offers barrier protection to steel which prevents the entry of chloride ions

- Excellent adhesion and it forms a lasting bond with the surface of the steel rebars
- High mechanical impact strength.


# 2.1.2. Epoxy Rebar Coating - Applications

Epoxy Coated TMT Rebars are used in concrete subjected to corrosive conditions. These may include exposure to deicing salts or marine environments. Protective rebar coatings help protect the rebar against corrosion in severe marine and corrosive environments. The coatings provide resistance against cathodic disbondment and corrosive agents such as sea water, harsh chemicals, acid rain, deicing salts, contaminated aggregate, airborne salt, spray, carbonation, and concrete additives. One of the major applications of coated rebars is in the construction industry.

In terms of end-user industry, the rebar coating market can be segmented into building & construction, oil & gas, and manufacturing. The rebar coating market is currently dominated by the building & construction industry.

Epoxy Coating Rebar finds applications in the following structures

- Underground buildings
- Bridges
- Pavements
- Offshore structures.
- Parking structures.
- Marine structures



#### 2.2. ESTIMATE OF DOMESTIC DEMAND

The demand for epoxy coated rebar is mainly from the construction industry. The demand estimates are based on the following:

- Local production
- Out of the overall output of Rebars produced in the country, 5% can be considered as the service that seeks for epoxy coating.
- While the general practice is to have own powder coating facility, typically the service is outsourced, as it is a non-core and specialized activity for rebar producers.

#### 2.2.1. Local Producers

No.	Company	Category	Capacity in Tons
1	Shadeed Iron and Steel	Rebar	1,400,000
2	Moon Steel (MISCO)	Rebar	1,200,000
3	Sharq Sohar Steel	Rebar	300,000
4	Hadid Majan LLC	Rebar	210,000
5	Muscat Steel Industries Co LLC	Rebar	400,000
6	Dawood Rebar	Rebar	1000
	TOTAL		3,511,000

# 2.2.2. Estimated Demand / Consumption

Year	2022
Capacity of Rebar Plants in Oman	3,511,000 Tons
Estimated Production (70% Capacity Utilization)	2,457,700 Tons
Estimated Demand for epoxy coating of rebar (around 5% of overall rebar production)	122,885 Tons

Based on the above, the demand for epoxy coating of rebar (around 5% of overall rebar production) shall be around 122,885 tons.

### 2.3. DEMAND PROJECTION

The future demand for the epoxy coating services is projected as below:

Year	2022	2023	2024	2025	2026	2027	2028
Demand (Tons)	122,885						
Projected Growth rate (%)		3%	3%	3%	3%	3%	3%
Projected Demand (Tons)		126,572	130,369	134,280	138,308	142,457	146,731

#### 2.4. COMPETITION ANALYSIS

There are no major standalone service providers for polymer coating of rebar in Oman. Middle East Conversion Industry LLC, which is part of Sohar Steel Group has a plant that provides Fusion Bonded Epoxy Coating for Rebars. The details of the other service providers are as detailed below.

# 2.4.1. Local Players

**Middle East Conversion Industry LLC** is located in Sohar Industrial Estate, Sultanate of Oman and belongs to Sohar Steel Group. The Plant provides (i) provision Fusion Bonded Epoxy Coating to Rebars as per ASTM Standard and (ii) manufactures Steel Weld Mesh as per British Standard.

Epoxy Coating plant uses high speed shot blasting machine to achieve surface cleanliness & surface texture and Italian equipments for corrosion resistant epoxy coating. The Bundles are wrapped in poly ethylene cover for better shielding.

#### 2.5. MARKETING MIX STRATEGY OF COMPETITORS

#### 2.5.1. Services

The polymer coated bars are typically coated with Polymers including polyester, polyurethane, polyester-epoxy and acrylics and are bought as per the end-user requirements.

# 2.5.2. Pricing

Based on the brief primary survey and on secondary research, the service cost are in the range of RO 65 – 70 per ton.

#### 2.5.3. Promotion

The polymer coated rebar are sold mainly through contacts with construction companies, distributors / dealers.

#### 2.5.4. Trade Credit

The industry practice is to offer a reasonable credit period depending on the credit worthiness of the client. Often discounts of 5 – 10 percent are also given to the clients.

#### 2.5.5. Distribution

The distribution process is through direct sales to contractors in the construction industry and to larger organizations seeking the product.

#### 2.6. Proposed Marketing Mix Strategy For The Company

#### 2.6.1. Product Mix

The project shall provide epoxy coating of rebar services. The services shall be based on the end user requirements and the specifications.

#### 2.6.2. Target Market

The project shall initially cater to the local demand and the target market groups should be mainly Building Contractors and Wholesalers.

# 2.6.3. Pricing

Based on the industry standards, the service charges for polymer coating of the rebar considered for the financial projections is around RO 63 per ton.

#### 2.6.4. Promotion

The company shall concentrate on building healthy personal contacts with various segments mainly in construction industry. The General Manager shall be responsible for sales as well. The manager shall build and retain long term relationships with customer segments. In addition, the unit would also promote and create awareness about its capabilities in handling various jobs to ensure customer confidence and improving market reaches / market penetration.

The social media platforms shall be effectively used and a specific website detailing the credentials and the capabilities of the project shall be developed.

The company will also consider the following promotional activities:

- Participation in Building Materials Fairs
- Advertisement in Electronic & print media
- Sales promotion programs

The company could also offer its customers a credit period of 60 days in-line with the industry norms.

#### 2.6.5. Distribution

The company would concentrate on direct marketing to the contractors.

# 2.7. PROJECTED MARKET SHARE

The unit with a servicing capacity of 25,590 MT per annum can effectively leverage its capability to service the target market.

DETAILS	2024	2025	2026	2027	2028
Projected Demand	130,369	134,280	138,308	142,457	146,731
Projected Production	12,283	15,354	19,193	20,472	21,752
Estimated Market Share in % (Local)	9.42%	11.43%	13.88%	14.37%	14.82%

#### 3. TECHNICAL ANALYSIS


#### 3.1. LOCATION

The proposed project can be located either at Sohar Industrial City or at the proposed Shinas Industrial City. The referred locations are taking proximity to raw material and the target market into consideration.

#### 3.2. MANUFACTURING PROCESS

Applying a rebar with a fusion-bonded epoxy protective coating is a four step process that involves the blasting, heating, coatings, and cooling of bars. Prior to applying the coating on the rebar, the rebar surface needs to be cleaned, which is done using the blasting of bars. The rebar is blast cleaned to obtain a near white metal finish. The process is carried out in a shot blaster, which utilizes shots and grits, an abrasive material to clean the rebar surface. The blasted rebar is then subjected to heat and is heated to around 230°C in an electric induction heater. The heated rebar is then passed through a coating booth and coated with the protective coating with the help of electrostatic charge. Coating particles are attracted toward the rebar surface due to the electrostatic charge, providing a uniform coating over it. Coating particles melt due to the hot rebar surface, thereby forming a film of coating over it. The rebar is then cooled in a cooling tunnel, where water is sprayed onto it.

The FBE powder Coating application has five essential stages:



Stage 1: Surface preparation - Airless (Wheel Blast) Shot Blasting Process

Shot Blast cleaning is the most commonly used method for preparation of steel surfaces. This effectively removes rust, scale, slats, and makes surface rough (rough surface is called profile). Profile increases the effective surface area of the steel. The cleanliness achieved is assessed to by Swedish standard, the common terminology of white-metal, near white-metal, etc. Typically, SA 2½. It is important to remove grease or oil contamination prior to blast cleaning. Solvent cleaning, burn-off, etc., are commonly used for this purpose. In the blast cleaning process, a blasting wheel uses centrifugal force to propel the abrasive against rebar in controlled direction, speed and quantity. The equipment is equipped with 4 blast wheels. 2 blast wheels are mounted on the top of the cabinet and positioned above the pass line of the work and the other 2 Blast wheels are mounted in the bottom of the cabinet positioned below the pass line of the rebar

# **Stage 2: Pre-heating - Induction heating**

Heating can be achieved by using several methods, but the most commonly used ones are "induction heating". Induction heating is the process of heating an electrically conducting object (usually a metal) by electromagnetic induction, where eddy currents are generated within the metal and resistance leads to Joule heating of the metal. An induction heater (for any process) consists of an electromagnet, through which a high-frequency alternating

current (AC) is passed. Heat may also be generated by magnetic hysteresis losses in materials that have significant relative permeability. The frequency of AC used depends on the object size, material type, coupling (between the work coil and the object to be heated) and the penetration depth. The steel part is passed through a high frequency alternating current magnetic field, which heats the metal part to the required FBE coating application temperature. Typical application temperature for a standalone FBE is 225° to 245°C. When used as a primer in a multi-layer polyolifine system, application may be dropped based on **FBE** manufacturer's temperature recommendations, in order to meet the "inter-coat adhesion" parameters.

# Stage 3: Fusion bonded epoxy coating

The FBE powder is placed on a "fluidisation bed". In a fluidization bed, the powder particles are suspended in a stream of air, in which the powder will "behave" like a fluid. Once the air supply is turned off, the powder will remain in its original form. The fluidised powder is sprayed onto the hot substrate using suitable spray guns. An electrostatic spray gun incorporates an ioniser electrode on it, which gives the powder particles a positive electric charge. The steel to be coated is passed through the powder stream on conveyor. The charged powder particles uniformly wrap around the substrate, and melts into a liquid form. The molten powder 'flows' into the profile and bonds with the steel. The molten powder will become a solid coating, when the 'gel time' is over, which usually occurs within few seconds after coating application. The resin part of coating will undergo cross-linking, which is known as "curing" under the hot condition. Complete curing is achieved depending on the FBE coating system, full cure can be achieved in less than one minute.

#### **Stage 4: Curing**

The molten powder becomes a solid coating, when the 'gel time' is over, which usually occurs within few seconds after coating application. The resin part of coating undergoes cross linking, which is known as 'curing' under the

hot condition. Complete curing is achieved either by the residual heat on the steel, or by the help of additional heating sources. Depending on the FBE coating system, full cure can be achieved in less than one minute to a few minutes in case of long cure FBE's. During curing time, the coating gets hardens to a solid.

#### **Stage 5: Water quenching**

The coated bars after curing are passed through a water tunnel. Water is sprayed on to the bars to cool them.

### Stage 6: Holiday testing

Once the rebar has passed through the cooling tank, it is tested with a holiday detection device that electrically examines the rebar for pinholes in the coating.

#### 3.3. LAND & BUILDING

A total building area required for the project is 6,100 Sq. m. The proposal is to take the building on lease @ RO 2.5 per square meter per month.

#### 3.4. MACHINERY

The major machinery required for the project is Powder Spraying Booth and the Curing Oven. Major suppliers are available in Europe, India and China.

The details of the main and auxiliary machineries required for the project is as detailed in Annexure 1.3.

# 3.4.1. Machinery Suppliers

The following table illustrates the details of rebar epoxy coating machinery supplier from where quotations were received.

No.	Detail

1 Patel Furnace & Forging Pvt Ltd

A/2-510, GIDC. Makarpura

Vadodara - 390010, Gujarat, India

Email - sales@pshotblast.com

Website: www.pshotblast.com

#### 3.5. PLANT CAPACITY

The capacity of the unit for rebar coating is around 25,590 tons at 16 hours production per day. The estimated coating capacity Utilization is as detailed in the following table:

Year	Year 1	Year 2	Year 3	Year 4
Installed Capacity (Tons)	25,590	25,590	25,590	25,590
Capacity utilization (%)	48%	60%	75%	80%
Estimated Production (Tons)	12,283	15,354	19,193	20,472

#### 3.6. VEHICLES

The vehicles are required for movement of raw materials and internal material movement. Details of Vehicles are provided in Annexure 1.4.

#### 3.7. RAW MATERIALS AND CONSUMABLES

Epoxy Powders are the main raw materials required for the project. The quantity and cost of raw materials including consumables are detailed in Annexure 2.1.

#### 3.8. UTILITIES

#### 3.8.1. Water

Water is required for Curing and Quenching and also for the Induction Heater in addition to water required for human consumption. It is estimated that 12,928 cubic metres of water is required per annum.

# 3.8.2. Electricity

Electricity is used for machine operations and for general purpose lighting. The connected load is around 2,444 kW. The annual consumption of electricity for the plant and other purposes works up to around 11,779,200 KWH at full capacity.

### 3.9. MANPOWER

It is estimated that 75 resources are required for the project considering 2 shift operation. The details are as follows:

S. No	Donostmont	No of persons		
5. 110	Department	National	Expat	
1	Production	17	48	
2	Administration & Accounts	7	1	
3	Sales	2	0	
Total		26	49	
			75	

#### 3.10. PROJECT IMPLEMENTATION

Being an SME project, the total expected time duration for implementation shall be around 12 months.

#### 4. FINANCIAL ANALYSIS

#### 4.1. PROJECT COST

The total cost of the project is estimated at RO 918,000. Details are given in Annexure – 1. The break-up is given below:

Details	Amount (RO)
Building	5,000
Plant & Machinery	598,000
Vehicles and Internal Transport	22,000
Furniture & Office Equipment	11,000
Pre- Operative Expenses	67,000
Contingency & Escalation	35,000
Sub Total	738,000
Working Capital	180,000
TOTAL CAPITAL	918,000

# 4.1.1. Land & Building

The total building area is around 6,100 Sq. An Industrial Shed will be taken on lease rental. Details are provided in Annexure 1.1 and 1.2.

### 4.1.2. Plant & Machinery

The total cost of plant and machinery is estimated at RO 598,000. Details are given in Annexure- 1.3.

### 4.1.3. Vehicles & Internal Transport

The total cost of vehicles and internal transport is estimated at RO 22,000. Details are given in Annexure- 1.4.

# 4.1.4. Furniture & Office Equipment

The total cost of furniture and office equipment is estimated at RO 11,000. Details are given in Annexure- 1.5.

# 4.1.5. Pre-Operative Expenses

The pre-operative expenses include expenses for feasibility study, interest during project implementation, salaries and wages of project staff, travel and communication, legal fees, audit fees and other miscellaneous expenses. The total pre-operative expenses are estimated at R.O 67,000. Details are given in Annexure- 1.6.

### 4.1.6. Contingency & Escalation

A provision of 5 % of the estimated cost of items including building, plant & machinery, vehicles etc., is provided in the Project cost towards price escalation and any unforeseen expenses. This works out to RO 35,000. Details are given in Annexure- 1.7

# 4.1.7. Working Capital

Following assumptions are made for computation of working capital.

Details	Period
Accounts Receivable	2 Months
Raw Materials	1 Month
Consumables & packing	1 Month
Utilities	1 Month
Factory Wages	1 Month
Administration Expenses	1 Month
Sales Expenses	1 Month
Work in Progress	3 Days
Finished Goods	5 Days
Finance Cost	1 Month
PAYABLES	
Raw Materials	1 Month

The working capital requirements for the first 4 years of operation are given below. The working capital requirement in the first year comes to RO 180,000. Details are given in Annexure 1.8.

Particulars	Year 1	2	3	4
Working Capital Requirement (RO '000)	180	201	263	274

#### **4.2.** MEANS OF FINANCE

It is proposed to finance the Project as indicated in the following table.

Means of Finance	Amount (RO)
Equity Capital (40% of Project Cost)	367,200
Term Loan at 3% interest rate (ODB)	442,800
Commercial Loan for Working Capital	108,000
TOTAL	918,000

It is proposed that the total project cost of RO 918,000 will be financed by owner's fund [equity] to the tune of RO 367,200 term loan from ODB with an interest of 3% for RO 442,800 and commercial borrowings for working capital at RO 108,000. The working capital loan is expected to carry interest @ 6% per annum.

### 4.3. COST OF SALES

The cost of sale has been projected for the first ten years of operation (Annexure-2) and those of first five years are summarized as below:

Figures are in RO '000)

Details	Year 1	Year 2	Year 3	Year 4	Year 5
Raw Materials	75	94	117	125	133
Utilities	174	218	272	291	309
Factory Wages	152	156	303	312	322
PRIME COST	401	468	693	728	763
Rent for Land	183	183	183	183	183
Factory Overheads	14	23	23	23	23
Misc. Factory Exp.	12	13	18	19	19
FACTORY COST	610	687	917	953	989
Admin. Salaries	85	89	93	98	103
Admin. Expenses	9	9	9	10	10
TOTAL ADMIN EXPENSES	93	98	102	107	112
Sales Salaries	17	17	18	18	19
Sales Expenses	1	1	1	1	1
Advert.& Business Promotion	15	19	24	26	27
Total sales & distribution costs	33	38	43	45	48
OPERATING COST	736	823	1063	1105	1149
Finance cost					
Int. on Institutional finance	13	13	11	9	7
Int. on working capital	6	6	6	6	6
Total finance cost	20	19	17	15	14
Non-cash expenses					
Depreciation	71	71	71	71	71
Prelim Expenses written off	67	0	0	0	0
Total Cost	894	913	1151	1192	1234

# 4.3.1. Raw Materials

The cost of raw materials & consumables works out to RO 156,255 at full capacity and the details are in Annexure 2.1.

#### 4.3.2. Utilities

The total cost of utilities for working in full capacity is RO 363,330. The basis of estimate is given in Annexure 2.2.

### 4.3.3. Salaries & Wages

The cost of salaries and wages in the third year of operation is RO 404,460 which will be escalated in the following years. However in year 1 and year 2 reduced manpower has been considered owing to reduced capacity utilization. Details are given in Annexure 2.3.

# 4.3.4. Factory Overheads

The annual expenses include repairs and maintenance, civil repairs, cost of spares, spare parts, insurance and vehicle expense and the same is estimated at RO 13,860 for the first year, RO 22,970 for the second and RO 23,115 for the third year. Details are given in Annexure- 2.4.

# 4.3.5. Administrative Expenses

The basis of estimates of administrative expenses inclusive of salaries & wages is given in Annexure 2.5 and it works out to RO 93,359. Administrative expense includes salaries and benefits, vehicle expenses, communication related expenses, stationery, etc.

### 4.3.6. Depreciation

Depreciation works out to RO 71,250. Depreciation calculation is given in annexure- 2.7. The following are the rates considered for the calculation of depreciation.

Assets	Life (years)	% of depreciation
Plant & Machinery	10	10
Vehicles and Internal Transport	4	25
Furniture & Office Equipment	5	20

#### 4.3.7. Loan & Interest Calculation

Interest rate for term loan and loan for working capital is taken at 3% and 6% respectively. Details of interest calculations are given in Annexure- 2.8.

#### 4.4. INCOME TAX

No income tax is provided as the new units are exempted from tax for the first five years and 15% tax is considered from 6<sup>th</sup> year onwards.

#### 4.5. SALES REALIZATION

The annual sales realization at installed capacity is given as annexure 3.1. The annual sales realization is provided below:

Detail	Year 1	Year 2	Year 3	Year 4	Year 5
Sales - RO '000	774	967	1209	1290	1370

#### 4.6. Cost Ratios

The major cost indicators as a percentage of sales realization are given in Annexure-3.

Details	Year 1	Year 2	Year 3	Year 4	Year 5
Raw Material / Total Sales	9.7%	9.7%	9.7%	9.7%	9.7%
Utilities / Total Sales	22.5%	22.5%	22.5%	22.5%	22.5%
Factory wages / Total Sales	19.6%	16.1%	25.1%	24.2%	23.5%
Prime Cost / Total Sales	51.8%	48.4%	57.3%	56.4%	55.7%
Rentals / Total Sales	23.6%	18.9%	15.1%	14.2%	13.4%
Factory exp. / Total Sales	3.3%	3.8%	3.4%	3.2%	3.1%
Factory Cost / Total Sales	78.8%	71.1%	75.8%	73.9%	72.2%
Administrative exp. / Total Sales	12.1%	10.1%	8.5%	8.3%	8.2%
Selling exp. / Total Sales	4.3%	3.9%	3.6%	3.5%	3.5%
Finance Cost / Total Sales	2.6%	2.0%	1.4%	1.2%	1.0%
Non-Cash exp. / Total Sales	17.9%	7.4%	5.9%	5.5%	5.2%
Total Cost / Sales	115.6%	94.4%	95.2%	92.4%	90.0%

Being an engineering unit with skilled operators employed, the factory wages other than Raw Material costs would be a major cost element.

### 4.7. NET PROFIT AND PROFITABILITY ANALYSIS

As per the financial projection in Annexure – 3, the venture is financially viable. The summary of the analysis is given under:

(Figures are in RO '000)

Details	Year 1	Year 2	Year 3	Year 4	Year 5
Revenue	774	967	1209	1290	1370
PBDIT	37	144	147	184	222
Depreciation	71	71	71	71	71
Finance Cost	20	19	17	15	14
Prelim. Exp. Written Off	67	-	-	-	-
Profit after tax	-121	54	58	98	137

### 4.8. KEY APPRAISAL CRITERIA

The viability of the project based on major appraisal criteria is given below.

Detail	Value
IRR on total investment	14.41%
IRR on Equity	22.63%
Payback period of Total Investment	6 years 7 months
Payback period on equity	5 years 9 months
DSCR	2.247

# 4.9. SENSITIVITY ANALYSIS

A sensitivity analysis has been carried out to determine the susceptibility of the project to changes in main variables.

Particulars	Original	Sales Volume down by 5%	RM Cost up by 5%	Sales Value down by 5%
IRR on Investment	14.4	10.4	13.8	8.4
IRR on equity	22.6	15.6	21.6	12.4

# 5. FACTORS TO CONSIDER BEFORE PROJECT IMPLEMENTATION

The following key factors have to be considered before implementing the project:

- The cost estimates of Plant and Machinery is based on budgetary offer received. The actual cost during implementation stage could change based on various factors like currency exchange rates, raw material price increase etc. It is advisable that the investor for the project should receive revised quotations from potential machinery suppliers before implementing the project.
- Capacity utilization is one of the major factors that shall determine the actual viability of the project.
- Quality is another major parameter to consider based on which customer build up shall happen over the period of years. Failure in delivering quality service to clients shall lead to the failure of the unit. It is recommended that required qualified technical resources are deployed for the successful operation of the project.

### 6. CONCLUSION

The IRR on Total Investment for the project is 14.4% and the IRR on Equity Investment is 22.6%.

The project has a healthy DSCR of 2.247.

Based on the various analysis carried out and as detailed above, the project is found to be technically feasible and financially viable.

Project Profile for Setting up a Rebar Epoxy Coating Plant
4 E' '1D ' ('
Annexures - Financial Projections
 25

#### **ANNEXURE-1** POLYMER POWDER COATING OF REBAR PROJECT **ESTIMATED PROJECT COST** S.No. Item Refer Amount Remarks App. (R.O.) PROJECT COST **A1** Land for Plant Site 1 1.1 0 On Lease Rental 2 Building etc. 1.2 5,000 On Lease Rental 3 Plant & Machinery 1.3 598,000 Estimates Vehicles and Int. Transport 4 1.4 22,000 Estimates 5 Furniture & Office Equip. 1.5 11,000 Estimates Pre-Operative Expenses 67,000 Estimates 6 1.6 7 Contingency & Escalation 1.7 35,000 Estimates Sub Total 738,000 738,000 WORKING CAPITAL 180,000 **A2** 918,000 **A3 TOTAL** В MODE OF FINANCE 367,200 40% of Total Project Cost 1 Equity 2 Term loan 442,800 810,000 3 Total 4 Working Capital Loan 108,000 TOTAL 918,000

	ANNEXURE- 1.2							
	POLYMER POWDER COATING OF REBAR PROJECT							
	ESTIMATED COS	ST OF BUILD	ING & CIVIL	WORKS				
S.No.	Item	Remarks						
		(SqM)	(R.O.)					
A	MAIN PLANT BUILDINGS							
1	Plant Area	2,000	=					
2	Factory Shed Storage	3,000	-					
3	Utility Area	1,000						
			_					
	Sub Total	6,000	-					
В	ADMIN BUILDING			On Lease Rental at RO 2.500				
1	Office Area	100	-	per Sq. M				
	Sub Total	100	-					
С	CIVIL WORKS							
1	Under Water Storage Tank		5,000					
	TOTAL	6,100	5,000					

	ANNEXURE- 1.3						
	POLYMER POWDER COATING OF REBAR PROJECT						
	ESTIMATED COS	T OF PLAN	T & MACHIN	IERY			
S.No.	Item	Q'ty	Rate	Amount	Remarks		
Α	MAIN PLANT AND MACHINERY		USD	RO			
				0.385			
1	Shot Blasting Machine	1	176,000		2 shifts		
2	Induction Heater	1	138,000				
3	Epoxy coating Booth	1	330,000				
	Fire Fighting System for Epoxy coating						
4	Booth	1	20,000				
5	Laboratory Instrument/Equipment	1	40,000				
6	Production Line		300,000				
	Sub Total Price Ex Works		1,004,000	386,540			
	Additional : P & F Charges		38,000	14,630			
8	Sub Total		1,042,000	401,170			
В	ELECTRIFICATION			100,293	25% of the Above		
С	Crane for Loading & Unloading of	2		4 000			
	rebars (Local)	2		4,000			
D	AT SITE COST						
1	Total Plant			505,463	Sum A+B+C		
2	Spares				Lumpsum		
3	Packing, Insurance Forwarding			,	5% of C1		
4	CIFCost				Sum C1 to C3		
5	Clearing & Transport to Site			· · · · · · · · · · · · · · · · · · ·	5% of C1		
6	At Site Cost			558,009	Sum of C4 to C5		
E	ERECTED COST						
1	At Site Cost			558,009			
2	Cost of erection - Local			40,117	10% of A8		
	TOTAL ERECTED COST			598,126			
	Say			598,000			

	ANNEXURE- 1.4								
	POLYMER POWDER COATING OF REBAR PROJECT								
	ESTIMATED COST OF VEHICLES & INTERNAL TRANSPORT								
S.No.	Item	Q'ty	Rate	Amount					
		(Nos.)		(R.O.)					
A	VEHICLES								
1	Pick up	1	10,000	10,000					
	Sub Total	1		10,000					
В	TRANSP. EQUIPMENT								
1	Forklift	1	10,000	10,000					
2	Registration, Painting, Spares etc			2,000	10% of the Above				
	Sub Total	1		12,000					
С	TOTAL	2		22,000					
	Say			22,000					

ANNEXURE- 1.5								
POLYMER POWDER COATING OF REBAR PROJECT								
ESTIMATED COST OF FURNITURE & OFFICE EQUIPMENT								
S. No.	Item		Amount	Remarks				
				(R.O.)				
Α	OFFICE							
1	P.C with Printer	4	500	2,000	Lumpsum			
2	Photocopier	1		1,000	Lumpsum			
3	Fax, Telephone	Set		500	Lumpsum			
4	Other Office Equipment	Set		200	Lumpsum			
5	Air Conditioners	4	250	1,000	Lumpsum			
6	Office Furnitures			1,000	Lumpsum			
	Sub Total			5,700				
В	FACTORY FURNITURE							
1	Work bench/Rack/Furniture etc			500				
	Sub Total			500				
C	ACCOMODATION FURNITURE							
1	Furniture / Fittings	Set		4,900	Lumpsum			
	Sub Total			4,900				
D	TOTAL			11,100 <b>11,000</b>				

		NEXURE- 1					
POLYMER POWDER COATING OF REBAR PROJECT ESTIMATED COST OF PRE-OPERATIVE EXPENSES							
		(R.O.)	(R.O.)				
1	Preliminary Expenses		2,000	Upto formation of Co.			
a	Salary & benefits -Supervisor	1,400		1 Month			
b	Salary & benefits - Production Staff	23,863		1 Month			
С	Salary & benefits - Admin. Staff	7,042		1 Month			
e	Visa, Passage etc.	10,400		For Expatriates at R.O. 400 / Person			
	Sub Total		42,705				
4	Financing Cost						
a	Institutional Loan Interest	6,642		At 3% for 6 months			
b	Mortgage Expenses	2,214		At 0.5 % on Institu: Loan			
С	Other Bank Charges	100		Lumpsum			
	Sub Total		8,956				
5	Communication		300	lumpsum			
6	Travel		500	Lumpsum			
7	Recruitment & Training Charges		500	Lumpsum			
8	Audit Fees, Legal Fees		500	Lumpsum			
9	Insurance			At 0.4 % of Plant & Bldg.			
10	Miscellaneous		200	Provision			
11	Supervision of Installation & Commissioning		8,085	USD 21,000			
12	Total		67,158				
	Say		67,000				

	ANNEXURE- 1,7 POLYMER POWDER COATING OF REBAR PROJECT								
	ESTIMATES OF CONTINGENCY AND ESCALATION								
S. No.	Item	Cost	Rate	Provision	Remarks				
		(R.O.)	(%)	(R.O.)					
A	FIXED ASSETS								
1	Land for Plant Site	-	0.0	-					
2	Building etc.	5,000	5.0	250					
3	Plant & Machinery	598,000	5.0	29,900					
4	Vehicles and Int. Transport	22,000	5.0	1,100					
5	Furniture & Office Equip.	11,000	5.0	550					
6	Pre- Operative Expenses	67,000	5.0	3,350					
	TOTAL			35,150					
				35,000	say				

	ANNEXURE- 1.8								
	POLYMER POWDER COATING OF REBAR PROJECT								
	ESTIMATES OF WORKING CAPITAL REQUIREMENTS								
S.No.	Item	Req.		Year 1	Year 2	Year 3	Year 4	Remarks	
					In R.C	0. '000			
1	Acct. Receivable	2	Months	126	140	180	187	Cost of sales - Non C Ex.	
2	Raw Materials	1	Month	6.3	7.8	9.8	10.4		
3	Utilities	1	Month	14.5	18.2	22.7	24.2		
4	Factory Wages	1	Month	13	13	25	26		
5	Admn. Expenses	1	Month	8	8	9	9		
6	Sales Expenses	1	Month	2.8	3.1	3.6	3.8		
7	Work in Progress	3	Day	5.0	5.6	7.5	7.8	At Factory Cost	
8	Finished Goods	5	Days	9.9	11.0	14.2	14.7	At total Cost-Non cash-Selling and Distrbn	
9	Finance Cost	1	Month	1.6	1.6	1.4	1.3	At Finance Cost	
10	Total			187	209	273	284		
11	Payables								
	Raw Materials	1	Months	6	8	10	10		
	Sub Total			6	8	10	10		
	Total			180	201	263	274		

	ANNEXURE- 2 POLYMER POWDER COATING OF REBAR PROJECT													
			]	POLYME	R POWDE	R COATIN	G OF REE	BAR PROJ	ECT					
						COST OF S	ALE							
	Year of Operation	1	2	3	4	5	6	7	8	9	10			
	Production	48%	60%	75%	80%	85%	85%	85%	85%	85%	85%			
No	Item					In R.	O.'000					Remarks		
1	Raw Material & Consumables	75	94	117	125	133	133	133	133	133	133	Ref. Annexure 2.1		
2	Utilities	174	218	272	291	309	309	309	309	309	309	Ref. Annexure 2.2		
3	Factory Wages	152	156	303	312	322	331	341	351	362	373	Ref Annexure 2.3		
4	PRIME COST	401	468	693	728	763	773	783	793	804	814	Sub total of 1 to 3		
5	Lease Rentals	183	183	183	183	183	183	183	183	183	183	RO 2.5 / sq. m ./ month		
6	Factory Overheads	14	23	23	23	23	23	23	23	23		Ref Annexure 2.4		
7	Misc. Factory Exp.	12	13	18	19	19	20	20	20	20	20	At 2 % of (6) & (7)		
8	FACTORY COST	610	687	917	953	989	999	1009	1019	1030	1041	Sub total of 5 to 7		
9	Admin. Salaries	85	89	93	98	103	108	113	119	125	131	Ref Annexure2.3&2.5		
10	Admin. Expenses	9	9	9	10	10	10	10	11	11	11	Ref Annexure 2.5		
11	Total Admin expenses	93	98	102	107	112	118	124	129	136	142	Sum (9) to (10)		
12	Sales Salaries	17	17	18	18	19	19	20	21	21	22	Ref Annexure2.3&2.6		
13	Sales Expenses	1	1	1	1	1	1	1	1	1		Ref Annexure 2.6		
14	Advert.& Business Promotion	15	19	24	26	27	27	27	27	27		2% on sales		
15	Total sales & dist: costs	33	38	43	45	48	48	49	49	50	51	Sum of (12 to 14)		
16	OPERATING COST	736	823	1063	1105	1149	1165	1181	1198	1216	1234	Sum(8)+(11)+(15)		
	Finance cost													
17	Int on Institutional finance	13	13	11	9	7	5	3	1	0	0	Ref Annexure 2.8		
18	Int on working capital	6	6	6	6	6	6	6	6	6	6	Ref Annexure 2.8		
19	Total finance cost	20	19	17	15	14	12	10	8	6	6	Sum (17)+(18)		
	Non cash expenses													
20	Depreciation	71	71	71	71	71	71	71	71	71	71	Ref Annexure 2.7		
21	Prelim Expenses written off	67	0	0	0	0	0	0	0	0	0	Ref Annexure 2.7		
22	COST OF SALE	894	913	1151	1192	1234	1248	1262	1277	1293	1312	Sum 16+19+20+21		

	ANI	NEXURE- 2.1												
	POLYMER POWDER C	OATING O	F REBAR PI	ROJECT										
	ESTIMATED COST OF RAW MATERIALS													
S. No.	S. No. Item Unit Qty Rate Amount I													
Α	RAW MATERIALS				(R.O.)									
1	Epoxy Powder of Different Types for Coating	Tons	512	193	98,522	USD 500 per Ton								
2	Shot Usage		512	58	29,556	USD150 per ton								
	SubTotal				128,078									
В	CONSUMABLES													
	Chemicals for Cleaning and Phosphating				25,616	20% of A1								
	SubTotal				25,616									
	TOTAL				153,694									
С	Packaging Materials				2,562	2% of RM								
	Grand Total				156,255									

	ANNEXURE- 2.2													
	POLYMER POWDER COATING OF REBAR PROJECT													
	ESTIMATED COST OF UTILITIES													
S.No.	S.No. Item Unit Qty Rate Amount Remarks													
					(R.O.)									
						At installed capacity								
1	Water	Cu M	12,928	0.770	9,954									
2	Electricity	KWH	11,779,200	0.030	353,376									
	TOTAL				363,330									

		ANN	EXURE- 2.3				
	POLYMER PO	WDER CO	OATING OF	REBAR PR	OJECT		
	ESTIMATES (	OF ANNU	AL SALAR	IES AND W	AGES		
S.No.	Item	No of p	ersonnel	Sala	ary	Annual	Remarks
		Expat Omani Expat Omani		onth)	RO		
		Expat	Omani	Expat	Omani		
A	PRODUCTION						
1	Plant Manager	1	0	1,000	-	12,000	
2	Production Supervisor	2		500		12,000	
3	QC Manager	1		600		7,200	
4	Lab Assistant		2	250	400	9,600	
5	Maintenace Engineer (Electrical & Mechai	4		450		21,600	
6	System Operators	10		250		30,000	
7	Coating Line Unskilled Workers	29	15	180	325	121,140	
8	Forklift Operator	1		250		3,000	
	Sub Total	48				216,540	
	<b>Total Manpower Cost</b>						
	Total Salary					216,540	
	Other Benefits					86,616	At 40 % of Salary
	Total Production Salary	48	17			303,156	
В	ADMINISTRATION & ACCOUNTS						
1	General Manager	0	1	-	1,200	14,400	
2	Finance Manager	1	0	1,000	-	12,000	
3	Accountant		1		450	5,400	
4	HR Manager/PRO		1		800	9,600	
5	HR Assistants		2		400	9,600	
6	Driver		1		400	4,800	
7	Security Guard		1		380	4,560	
	Sub Total					60,360	
	Other Benefits					24,144	At 40 % of Salary
	Total Cost	1	7			84,504	
С	SALES						
a	Sales						
1	Sales Executives		2	500	600	12,000	
	Sub Total					12,000	
	Other Benefits					4,800	At 40 % of Salary
	Total Cost	0	2			16,800	
D	GRAND TOTAL	49	26			404,460	
		19				101,100	
	Omanisation		35%				

	ANNEXURE- 2.4													
	POLYMER POWDER COATING OF REBAR PROJECT													
	ESTIMATES OF ANNUAL FACTORY EXPENSES													
S. No.	S. No. Item Year Year Remarks													
		1	2	3										
1	Repairs & Maintenance	2,990	2,990	2,990	At 0.5 % of erected cost of Plant and Machinery									
2	Civil Repairs	50	100	150	At 1 %, 2%,3% of cost of Building and Civil Works									
3	Spare Parts	2,990	11,960	11,960	At 0.5%, 2.0% and 2.0% of 'at-site' cost of P & M									
4	Insurance	6,030	6,030	6,030	At 1 % of cost Building, Plant and Machinery									
5	Vehicle Expenses	1,800	1,890	1,985	At RO 150 per forklift per month increased by 5% annually									
	TOTAL	13,860	22,970	23,115										

		ANNEXURE-	2.5											
	POLYMER POWDER COATING OF REBAR PROJECT													
	ESTIMATES OF ANNUAL ADMINISTRATIVE EXPENSES													
S. No.	Item	Amount	Remarks											
		(R.O.)	(R.O.)											
1	Salaries & Benefits		84,504											
2	Vehicle Expenses & Petrol													
a	Pick up	1800		At R.O. 150/Month each										
		0												
	Sub Total		1,800											
3	Telephone, Fax etc.		1,200	At R.O. 100/Month										
4	Stationery		1,200	At R.O. 100/Month										
5	Legal, Audit Fees		500	Lumpsum										
6	Registratioin & Renewals		500	Lumpsum										
7	Insurance		3,355	Lumpsum										
8	Other Expenses		300											
	Total		93,359											

	ANNEXURE- 2.6												
	POLYMER POWDER COATING OF REBAR PROJECT												
	ESTIMATES OF ANNUAL SALES EXPENSES												
S. No	. Item	Amount	Remarks										
		(R.O.)											
1	Salaries	16,800	See Annexure 2.3										
2	Travel	500	Lumpsum										
3	Miscellaneous Expenses	500	Lumpsum										
	Total	17,800											

		ANNEX	URE- 2.7											
	POLYMER POWDER COATING OF REBAR PROJECT DEPRECIATION CALCULATIONS													
	DEPI	RECIATION	CALCULA	TIONS										
	Item	Cost	Rate	S.V.	Amount	Renewals								
			(%)	(R.O.)	(R.O.)									
Α	FIXED ASSETS													
1	Land for Plant Site	0	0	0	-	Nil								
2	Building etc.	5000	5	2500	250	Nil								
3	Plant & Machinery	598000	10	0	59,800	Year 11								
4	Technical Know-How	0	10	0	-	Nil								
5	Vehicles and Int. Transp.	22000	25	11000	5,500	Years 5, 9								
6	Furniture & Office Equip.	11000	20	0	2,200	Years 6, 11								
7	Contingency & Escalation	35000	10	0	3,500	Nil								
8	Sub Total	671000		13500	71,250									
В	PRELIM &PRE OPE: EXP	67000	100	0	67,000	Nil								
C	WORKING CAPITAL													
1	Working Capital	273634	0	273634	=									
D	TOTAL			287,134	138,250									
	Less Balance Loan			108,000										
E	SALVAGE VALUE			179,134										
	Note: S.V. = Salvage Value at t	he end of 10t	h year.											

			A	NNEXURE	E- 2.8									
						AR PROJEC	CT CT							
	LOAN & INTEREST CALCULATIONS													
		7	Term Loan		WC	Loan	Annual							
No	Year	Prn	Int	Rep	Prn	Int	Int	Rep						
	7		3%			6%								
1		443	6.6	0	108	3.2								
2	1	443	6.6	0	108	3.2	19.8	0						
3		443	6.6	32	108	3.2								
4	2	411	6.2	32	108	3.2	19.3	63						
5		380	5.7	32	108	3.2								
6	3	348	5.2	32	108	3.2	17.4	63						
7		316	4.7	32	108	3.2								
8	4	285	4.3	32	108	3.2	15.5	63						
9		253	3.8	32	108	3.2								
10	5	221	3.3	32	108	3.2	13.6	63						
11		190	2.8	32	108	3.2								
12	6	158	2.4	32	108	3.2	11.7	63						
13		127	1.9	32	108	3.2								
14	7	95	1.4	32	108	3.2	9.8	63						
15		63	0.9	32	108	3.2								
16	8	32	0.5	32	108	3.2	7.9	63						
17		0	0.0	0	108	3.2								
18	9	0	0.0	0	108	3.2	6.5	0						
19		0	0.0	0	108	3.2								
20	10	0	0.0	0	108	3.2	6.5	0						

	ANNEXURE- 3													
	POLYMER POWDER COATING OF REBAR PROJECT													
	ESTIMATED WORKING RESULTS													
	Year of Operation													
	Production	48%	60%	75%	80%	85%	85%	85%	85%	85%	85%			
No	Item					In R.O.'(	000					Remarks		
1	<b>Operating Cost</b>	736	823	1063	1105	1149	1165	1181	1198	1216	1234	Ref Annexure 2		
2	Expected Sales	774	967	1209	1290	1370	1370	1370	1370	1370	1370			
3	Profit before Int & dep	37	144	147	184	222	206	189	172	155	136	Sum of (2-1)		
4	Depreciation	71	71	71	71	71	71	71	71	71	71	Ref Annexure 2.7		
5	Finance Cost	20	19	17	15	14	12	10	8	6	6	Ref Annexure 2.8		
6	Operating profit	-54	54	58	98	137	123	108	93	77	59	Sum of (3 - 4 - 5)		
7	Other income if any													
8	Prelim Expenses written off	67	-	-	-	-	-	-	-	-	=	Ref Annexure 2.7		
9	Profit/Loss before tax	-121	54	58	98	137	123	108	93	77	59	Sum of (6 - 7 - 8)		
10	Income Tax	0	0	0	0	0	18	16	14	12	9	15% on profit from Year 6		
11	Profit after tax	-121	54	58	98	137	104	92	<b>79</b>	65	50			
12	Statutory reserve		5	6	10	14	10	9	8	7	5			
13	Profit for appropriation	-121	49	52	88	123	94	83	71	59	45			
14	Dividend	0	0	0	0	0	0	0	0	0	0			
15	General reserve	-121	49	52	88	123	94	83	71	59	45	Difference (13) - (14)		
16	Net cash accruals	18	125	129	169	208	176	163	150	137	121			

		ANNEXURE- 3	3.1											
	POLYMER POWDER COATING OF REBAR PROJECT													
	ESTIMATES OF SALES REALISATION													
S.No.	Item	Quantity of Material Coated in Tons	Rate	Amount	Remarks									
Per Annum RO (R.O.)														
A	Income													
a	From Powder Coating	25,590	63	1,612,170										
	TOTAL			1,612,170										

	ANNEXURE- 4												
POLYMER POWDER COATING OF REBAR PROJECT													
			INT	ERNAL I	RATE OF	RETUR	N ON TO	OTAL CA	APITAL				
	Year of Operation         1         2         3         4         5         6         7         8         9         10												
	Production		48%	60%	75%	80%	85%	85%	85%	85%	85%	85%	
No	Item					In	R.O.'000	)					Remarks
Α	CASH INFLOW												
1	Net Profit bef. Tax		-121	54	58	98	137	123	108	93	77	59	Refer Annexure - 3
2	Depreciation	0	71	71	71	71	71	71	71	71	71	71	Ref Annexure 2.7
3	Prelim Exp written off		67	0	0	0	0	0	0	0	0		Ref Annexure 2.7
4	Finance Cost	0	20	19	17	15	14	12	10	8	6		Ref Annexure 2.8
5	Salvage Value	0	0	0	0	0	0	0	0	0	0		Ref Annexure 2.7
6	Sub Total	0	37	144	147	184	222	206	189	172	155	1120	Sum of A1 to A5
В	CASH OUTFLOW												
1	Capital Project expenditure	671	0	0	0	0	22	11	0	0	22	0	Refer Annexure - 1
2	Other normal cap exp	67	0	0	0	0	0	0	0	0	0	_	Refer Annexure - 1
3	Working Capital	180	0	21	62	0	0	0	0	0	0		Refer Annexure - 1
4	Income Tax		0	0	0	0	0	18	16	14	12		Refer Annexure - 3.2
5	Sub Total	918	0	21	62	0	22	29	16	14	34	9	Sum of B1 to B4
C	NET CASHFLOW (AT)	-918	37	123	84	184	200	176	173	158	121	1111	
D	NETCASH FLOW(PT)	-918	37	123	84	184	200	195	189	172	133	1120	
E	INTERNAL RATE OF RETU	RN ON T	OTAL I	NVESTN	<b>IENT</b>						14.41	%	

	ANNEXURE- 5														
	POLYMER POWDER COATING OF REBAR PROJECT														
		IN	TERNA	L RATE	OF RET	TURN O	N EQUI	TY CAP	ITAL (A	FTER T	AX)				
	Year of Operation	0	1	2	3	4	5	6	7	8	9	10			
	Production		48%	60%	75%	80%	85%	85%	85%	85%	85%	85%			
No	Item					Iı	n R.O.'00	00					Remarks		
Α	CASH INFLOW														
1	Net Profit before Tax	0	-121	54	58	98	137	123	108	93	77		Refer Annexure- 3		
2	Depreciation	0	71	71	71	71	71	71	71	71	71	71	Refer Annexure - 2.7		
3	Prelim Exp written off	0	67	0	0	0	0	0	0	0	0		Refer Annexure - 2.7		
4	Salvage Value	0	0	0	0	0	0	0	0	0	0		Refer Annexure - 2.7		
5	Sub Total	0	18	125	129	169	208	194	179	164	148	1113	Sum of A1 to A4		
В	CASH OUTFLOW														
1	Equity	367	0	0	0	0	0	0	0	0	0	0	Refer Annexure - 1		
2	Fixed Assets	0	0	0	0	0	22	11	0	0	22	0	Refer Annexure - 1		
3	Working Capital	0	0	21	62	0	0	0	0	0	0	0	Refer Annexure - 1		
4	Loan Instalment	0	0	63	63	63	63	63	63	63	0	0	Refer Annexure - 2.8		
5	Income Tax	0	0	0	0	0	0	18	16	14	12	9	Refer Annexure - 3.1		
6	Sub Total	367	0	84	125	63	85	93	79	77	34	9	Sum of A1 to A5		
C	NET CASHFLOW	-367	18	41	4	106	123	101	100	87	115	1104			
D	INTERNAL RATE OF I	NVEST			22.63	%									

ANNEXURE- 6													
			POLY	MER POV	VDER CO	ATING O	F REBAR P	ROJECT					
				PROJECT	ΓED CAS	H FLOW S	TATEMEN	JT T					
Year of Operation		1	2	3	4	5	6	7	8	9	10		
Production		48%	60%	75%	80%	85%	85%	85%	85%	85%	85%		
Nos	000												
Item	In R.O.'000												
A CASH INFLOW													
CASH INFLOW													
Equity	367	0	0	0	0	0	0	0	0	0	0	Ref Annexure 1	
Profit bef tax & int		-101	73	75	113	150	134	118	101	83	65	Ref Annexure 3	
1	0	71	71	71	71	71	71	71	71	71		Ref Annexure 2.7	
		67	-	_	-	-	-	_	-	-		Ref Annexure 2.7	
	0	0	0	0	0	0	0	0	0	0		Ref Annexure 1	
Increase in Bank Term Loan		0	0	0	0	0	0	0	0	0		Ref Annexure 1	
		0	0	0	0	0	0	0	0	0	0	Ref Annexure 1	
												Ref Annexure 3	
Sub Total	918	37	144	147	184	222	206	189	172	155	136	Sum of A1 to A8	
CASH OUTELOW													
	671	0	0	0	0	22	11	0	0	22	0	Ref Annexure 1& 2.7	
, ,		U	U	U	U	22	11	U	U		U	Ref Annexure 1& 2.7	
1 1		0	21	62	0	0	0	0	0	0	0	Ref Annexure 1.7	
)												Ref Annexure 2.8	
	U									_	0	INCI MILIEAUIE 2.0	
		-	•	-			-	-		-	0	Ref Annexure 2.8	
					-				-			Ref Annexure 2.8	
1	0			_	0							Ref Annexure 3.2	
	0	0	0	0	0	0	0	0	0	0		Provision	
	918	20	104	143	79	99	104	89	85	40		Sum of B1 to B10	
OPENING BALANCE	0	0	18	58	62	168	291	392	492	579	694		
SURPLUS	0	18	41	4	106	123	101	100	87	115	121	Difference(A9)-(B11)	
CLOSING BALANCE	n	18	58	62	168	201	302	492	579	694	<b>815</b>		
	Production Nos  Item  CASH INFLOW Equity Profit bef tax & int Depreciation Prel exp written off Increase in Other term loan Increase in Bank Term Loan Increase in W C loan Other income Sub Total  CASH OUTFLOW Capital Project expenditure Other normal cap exp Increse in Working Cap: Decrease in Institu:Loan Decrease in Other term loan Interest on term loans Interest on work cap loan Income Tax Dividend Sub Total	Production Nos 000  Item  CASH INFLOW  Equity 367  Profit bef tax & int  Depreciation 0 Prel exp written off Increase in Other term loan 10 Increase in Bank Term Loan 443 Increase in W C loan 108 Other income 0 Sub Total 918  CASH OUTFLOW  Capital Project expenditure 671 Other normal cap exp 67 Increse in Working Cap: 180 Decrease in Institu:Loan 0 Decrease in Other term loan Interest on term loans Interest on work cap loan Income Tax 0 Dividend 0 Sub Total 918  OPENING BALANCE 0  SURPLUS 0	Nos	Year of Operation	Year of Operation	Year of Operation	POLYMER POWDER COATING O	Year of Operation	Year of Operation	POLYMER POWDER COATING OF REBAR PROJECT	Year of Operation	Vear of Operation	

						ANNE	EXURE- 7						
				POLYM	ER POWI	DER COA	ATING O	F REBAR	PROJEC	T			
					PROJI	ECTED B	ALANCE	SHEET					
	Year of Operation		1	2	3	4	5	6	7	8	9	10	
	Production		48%	60%	75%	80%	85%	85%	85%	85%	85%	85%	
No	Item					Iı	n R.O.'000	)					Remarks
A	ASSETS EMPLOYED												
1	Fixed Assets												
a	Gross Fixed Assets	671	671	671	671	671	693	704	704	704	726	726	Refer Annexure - 2.7
b	Preliminary expenses	67	0	0	0	0	0	0	0	0	0	0	Refer Annexure- 2.7
С	Acc. Depreciation	0	71	143	214	285	356	428	499	570	641	713	Refer Annexure - 2.7
d	Net Fixed Assets	738	600	529	457	386	337	277	205	134	85	14	
2	Current Assets												
a	Cash	0	18	58	62	168	291	392	492	579	694	815	Refer Annexure - 4
b	Other Cur. Assets	180	180	201	263	263	263	263	263	263	263	263	Refer Annexure - 1.7
С	Total Cur. Assets	180	198	260	326	431	554	655	755	842	957	1078	
3	Less: Cur. Liabilities	0	0	0	0	0	0	0	0	0	0	0	
		918	797	788	783	817	891	932	960	976	1042	1091	
В	FINANCED BY												
1	Equity	367	367	367	367	367	367	367	367	367	367	367	Refer Annexure - 1
2	Statutory reserve		0	5	11	21	35	45	54	62	69	74	
3	General reserves	0	-121	-72	-20	68	191	285	368	439	498	543	Cu.NP-Cu.Divident
4	Other term loan	0	0	0	0	0	0	0	0	0	0	0	Refer Annexure - 2.8
5	Institutional Finance	443	443	380	316	253	190	127	63	0	0	0	Refer Annexure - 2.8
6	Bank Borrowings	108	108	108	108	108	108	108	108	108	108	108	Refer Annexure - 2.8
		918	797	788	783	817	891	932	960	976	1042	1091	

				ANN	EXURE- 8									
	POLYMER POWDER COATING OF REBAR PROJECT													
	RATIO ANALYSIS													
	Years of Operation	1	2	3	4	5	6	7	8	9	10			
A	COST RATIOS													
1	Raw Material / Total Sales	9.7%	9.7%	9.7%	9.7%	9.7%	9.7%	9.7%	9.7%	9.7%	9.7%			
2	Utilities / Total Sales	22.5%	22.5%	22.5%	22.5%	22.5%	22.5%	22.5%	22.5%	22.5%	22.5%			
3	Factory wages / Total Sales	19.6%	16.1%	25.1%	24.2%	23.5%	24.2%	24.9%	25.6%	26.4%	27.2%			
4	Prime Cost / Total Sales	51.8%	48.4%	57.3%	56.4%	55.7%	56.4%	57.1%	57.9%	58.6%	59.4%			
5	Rentals / Total Sales	23.6%	18.9%	15.1%	14.2%	13.4%	13.4%	13.4%	13.4%	13.4%	13.4%			
6	Factory exp. / Total Sales	3.3%	3.8%	3.4%	3.2%	3.1%	3.1%	3.1%	3.1%	3.2%	3.2%			
7	Factory Cost / Total Sales	78.8%	71.1%	75.8%	73.9%	72.2%	72.9%	73.6%	74.4%	75.2%	76.0%			
8	Administrative exp. / Total Sales	12.1%	10.1%	8.5%	8.3%	8.2%	8.6%	9.0%	9.4%	9.9%	10.4%			
9	Selling exp. / Total Sales	4.3%	3.9%	3.6%	3.5%	3.5%	3.5%	3.6%	3.6%	3.7%	3.7%			
10	Finanace Cost / Total Sales	2.6%	2.0%	1.4%	1.2%	1.0%	0.9%	0.7%	0.6%	0.5%	0.5%			
11	Non-Cash exp. / Total Sales	17.9%	7.4%	5.9%	5.5%	5.2%	5.2%	5.2%	5.2%	5.2%	5.2%			
12	Total Cost / Sales	115.6%	94.4%	95.2%	92.4%	90.0%	91.0%	92.1%	93.2%	94.4%	95.7%			
В	PROFITABILITY RATIOS													
1	PBDIT / Sales	4.8%	14.9%	12.1%	14.3%	16.2%	15.0%	13.8%	12.6%	11.3%	9.9%			
2	Operating profit / Sales	-6.9%	5.6%	4.8%	7.6%	10.0%	9.0%	7.9%	6.8%	5.6%	4.3%			
3	PAT / Sales	-15.6%	5.6%	4.8%	7.6%	10.0%	7.6%	6.7%	5.8%	4.8%	3.6%			
4	PAT / Investment	-14.9%	6.7%	7.2%	12.1%	16.9%	12.9%	11.4%	9.8%	8.1%	6.1%			

	ANNEXURE- 9											
	POLYMER POWDER	COATING	OF REBA	R PROJECT								
	BREAF	CEVEN AN	ALYSIS									
S. No.	Item	Year 1	Year 6	Remarks								
		In R.C	D. '000									
Α	FIXED COST											
1	Production Wages	152	331	Refer Annexure - 2								
2	Factory Overheads	197	206	Refer Annexure - 2								
3	Misc. Factory Exp.	12	20	Refer Annexure - 2								
4	Admin. Expenses	93	102	Refer Annexure - 2								
5	Sales Expenses	33	48	Refer Annexure - 2								
6	Depreciation	71	71	Refer Annexure - 2								
7	Prelim. Expenses written off	67	0	Refer Annexure - 2								
8	Financing Cost	20	12	Refer Annexure - 2								
9	Income Tax	0	18	Refer Annexure - 2								
10	Sub Total	645	809									
В	VARIABLE COST											
1	Raw materials	<i>7</i> 5	133	Refer Annexure - 2								
2	Utilities	174	309	Refer Annexure - 2								
3	Misc. Expenses	0	0									
4	Sub Total	249	442									
С	SALES	774	1370	Refer Annexure - 3								
D	CONTRIBUTION	524	929	Difference C - B								
E	BREAK EVEN POINT	59.0	74.0	As % of Plant Capacity								
				1 7								
F	CASH BEP	46.4	67.5	As % of Plant Capacity								

	ANNEX												
	POLYMER POWDER COAT			[									
	SENSITIVITY ANALYSIS (IRR FOR 10 YEARS)  Projection Change in One												
C N	, ,												
S. No.	Item	No Change	Var	riable at a T	ime								
A	VARIABLE		Volume	R. M	Sales								
			Nos	Cost	Value								
	Value- Original												
В	PESSIMISTIC												
	Change		-5%	5%	-5%								
C	OPTIMISTIC												
	Change		5%	-5%	5%								
D	I R R - PESSIMISTIC PROJECTION												
1	I R R on Investment	14.4	10.4	13.8	8.4								
2	I R R on Equity	22.6	15.6	21.6	12.4								
E	I R R - OPTIMISTIC PROJECTION												
1	I R R on Investment	14.4	18.3	15.0	20.1								
2	I R R on Equity	22.6	29.8	23.6	33.3								

	ANNEXURE- 11													
		P	OLYMER	POWDER	COATIN	G OF REB	AR PROJ	ECT						
	DEBT SERVICE COVERAGE RATIO													
	Years of Operation	0	1	2	3	4	5	6	7	8	9			
	Production in (%)		48%	60%	75%	80%	85%	85%	85%	85%	85%			
	Nos	000												
No	Item	In R.O.'000												
1	Profit after tax		-121	54	58	98	137	104	92	79	65			
2	Depreciation		71	71	71	71	71	71	71	71	71			
3	Prelimnery exp. Written off		67	0	0	0	0	0	0	0	0			
4	Interest		20	19	17	15	14	12	10	8	6			
5	Total		37	144	147	184	222	187	173	158	143			
1	Annual repayment		0	63	63	63	63	63	63	63	0			
2	Interest		20	19	17	15	14	12	10	8	6			
3	Total		20	83	81	79	77	75	73	71	6			
	D.S.C.R		1.89	1.75	1.82	2.34	2.88	2.50	2.37	2.22	22			
	WT. AVERAGE D.S.C.R	2.247												